

### **TENDER NOTICE**

Baroda UP Bank, Regional Office Khalilabad, intends to invite Tenders from furnishers/applicants for the proposed **Furnishing/interior and electrical works of our branch- Mukhlishpur,** at khalilabad as per enclosed offer Bid/BOQ proforma.

The completion period of work will be 21 days from the date of issue order. The work shall be executed under the supervision of our consulting architect and as per specifications demonstrated in Offer Bid proforma/BOQ.

Offer Bid proforma /BOQ is attached with notice. Offer should be valid for a minimum period of 120 days from the last date of submission. No brokerage shall be paid. The sealed cover marked as Bid super scribing "FURNISHING WORK BID FOR MUKHLISHPUR, BRANCH" be put in once sealed envelope and other sealed cover marked as Bid super scribing "ELECTRICAL WORK BID FOR MUKHLISHPUR BRANCH" be put in another one sealed envelope.

Both sealed envelope addressed and submitted to

"Regional manager Baroda UP Bank Regional Office Khalilabad Mehdawal Road bypass, Sant kabir nagar-272175 Mo-9161235782"

Within 21 days from the day of publication of this advertisement on or before 15.02.2022 by 04.00 PM

Any decision taken by bank at any point of time in connection with this process shall be final and conclusive and no claim or dispute from any quarter in that regard shall be entertained.

Date: 24.01.2022

Enclosed: Offer Bid Proforma/BOQ

Regional Head

# **EUCEE & ASSOCIATES**

# DETAIL TENDER FOR ELECTRICAL WORK FOR BARODA U.P. BANK AT MOKHALISPUR BRANCH, SANT-KABIR NAGAR.

S.No.	Description of Items	Qty.	Unit	Rate	Amount
1-	Supply & Fixing of FP MCCB 125Amp 25ka with Enclosure near Energy Meter before Main Panel.		Set.		.xmount
	Main Panel Box: Fabrication Delivery & Installation in Cubical Type 20 gauge Metal sheet suitable for 415V with Digital Display Multifunctional Meter, "DANGER" Board, Current Transfermer and LED Indication Lamp comprising the following: MCCB 125A 25ka FP- 1No. Copper Bus-Bar- 1Set. Changeover Switch 125Amp- 1No. for Incoming. And for Out Going: Copper Bus-Bar- 1Set. MCCB 63Amp 25ka FP- 2No (for AC & UPS).	11	No.		
	Supply & Fixing of <b>TPN MCB DB 4way Double Door</b> with 63Amp FP RCCB 300ma as Incoming and suitable load rating SPMCBs as per requirment for Light/Fan, UPS & AC.	2 1	Nos.		
	Supply & Fixing of SPN MCB DB 12way Double Door with 40Amp DP RCCB 300ma as Incoming and suitable load rating SPMCBs as per requirment for Light/Fan, UPS & AC.	3 1	Nos.		
	Supply & Drawing Circuit line by (2x6+1x2.5)Sq.mm FRLS PVC Insulated Copper Wire in PVC Pipe with All accessories fitted Conciled or Open as per site instruction by Architect for Sub Mains Panel to TPN.	32 1	Mtr.		
] , i	Supply & Drawing Circuit line by (2x4+1x2.5)Sq.mm FRLS PVC Insulated Copper Wire in PVC Pipe with All accessories fitted Conciled or Open as per site instruction by Architect for UPS, SPNDB, Glow Sign Board & AC.	150 1	Mtr.		
	Supply & Drawing Circuit line by (2x2.5+1x1)Sq.mm FRLS PVC Insulated Copper Wire in PVC Pipe with All accessories fitted Conciled or Open as per site Instruction by Architect for All Circuit wiring.	188 1	Mtr.		
H	Supply & Drawing Circuit line by (2x1.5+1x1)Sq.mm FRLS PVC Insulated Copper Wire in PVC Pipe with All accessories fitted Conciled or Open as per site Instruction by Architect for PC Circuit wiring.	160 1	Mtr.		
5440	Supply & Fixing 40Amp DP MCB with Enclosure for UPS Incoming and Outgoing.	2 1	Nos.		

.No.	Discription of Items	Qty. Unit	Rate	Amount
	B/F- Before Page		Rs.	0.00
10-	Light Fan Point Wiring by 1.5 Sq.mm Copper wire		33334321	
	with all accessories like Switch, Socket, Top & Cover			
- 1	Plate as per Following			
a-	Single Point controlled by Single Switch.	40 Point.		
b-	Double Point controlled by Single Switch.	8 Point.		
c-	Socket 6Amp Point controlled by Single Switch.	8 Point.		
d-	Call Bell controlled by Bel Push.	1 No.		
11-	Fan Point controlled by <b>Electronic Regulator</b> & Switch.	8 Nos.		
12-	Supply & Fixing for Raw Power 6/16Amp Socket with Switch.	6 Nos.		
13-	Supply & Fixing for PC Terminal Power Board 4way 6Amp Socket with Switch.	6 Set.		
14-	Supply & Fixing Air-conditioner Starter with 20Amp SPN MCB and Socket including Power Top.	2 Nos.		
15-	Earthing Work: Supply & Fixing Maintenance Free Electrode Earth with Backfil compound chemical Bag resistance shuld be less than 2.0 Ohms specification as per IS 3043/1987 complete in all respects.	2 Job.		
16-	Supply & Laying 6Sq.mm Copper Wire for Earthing Circuit Earth Place to UPS, Main Panel & all DBs.	50 Mtr.		
17-	Supply & Fixing Down Rod 2ft. Long for Ceiling Fan Hanging.	8 Nos.		
18-	Supply & Fixing Telephone single Pair wiring at Two Circuit.	30 Mtr.		
19	Supply & Drawing LAN Cabling by CAT-6 in PVC Conduit Pipe.	100 Mtr.		
20-	Supply & Fixing RJ-11 Telephone Jack Panel complete in all respects.	2 No.		
21-	Re-fixing Data Info-Rack 19" 9U complete in all respects.	1 No.		
22	- Supply & Fixing Networking Information Outlet Box (I.O. Box) complete in all respects.	6 No.		
23	- Supply & Fixing <b>RJ-45 connector</b> at LAN Cable one end complete in all respects.	6 No.		

S.No.	3						
1.1.10.	Description of Items	Qty.	Unit	Rate	Amount		
2.1	B/F- Before Page			Rs.	0.00		
24-	Re-Fixing Fast Ethernet Switch 24 Port as per Adviby Architect.	ce 1	No.	7457	0.00		
25-	Supply & Fixing Patch Cord (CAT-6) Digilink/HCL or I-Bell 3'long.	4	No.				
26-	Supply & Fixing Patch Cord (CAT-6) Digilink/HCL or I-Bell 7'long.		No.				
27-	Re-Fixing of old Ceiling fan after repairing.	2	Nos.				
28-	Supply & fixing of new ceiling fans of 1200mm and make Havell's/ Crompton	6	Nos.				
29-	Supply & Fixing Wall Fan 400mm.	2	Nos.				
30-	- Supply & Fixing Exhaust Fan 300mm.	2	Nos.				
31	- Supply & Fixing 36 W 2'x2' LED Square Panel.	6	Nos.				
32	- Supply & Fixing 12W LED Down Lighter.	6	Nos.				
33	- Supply & Fixing of Batten LED fitting 18W.	4	Nos.				
				Total Rs.			
	of Approved Make:-	/ TT 111-	HCI	/ DD Kab	lo.		
Cop	per Wire FRLS Grade : Finolex/ Polycab			KK Kab	ie.		
Elec	tric Cable : Havell's/ Polycal	/ Gloster	•				
ELC	CB, MCCB & RCCB : L&T/ Siemens/ C	GE/ Havel	l's/ AI	BB/ HPL/	Leagrand.		
	Bs, DBs, SFUs : L&T/ Siemens/ C	GE/ Have	ll's/ AI	BB/ HPL/	Leagrand.		
Mod	dular Switch, Sockets : Anchor Roma/ C	: Anchor Roma/ Crabtree/ MK/ Polycab.					
Ear	thing for Bldg. & UPS : Earth Electrode	IS:3043-1	1978 C	hemical I	Earthing.		
PVO	C Conduit Pipe : AKG/ Precision/	Polycab/	Asian	•			
Tele	ephone & Data Cable : Digilink/ Finoles	/ Polycat	/ Hav	ell's/ HCI	/ RR Kable.		
Lug	: Dowells/ Jainson	or Equiv	velents	•			

Date: 17.01.2022

Metal Clad Sockets

RIVASTAVA)

BARODA U.P. BANK

: Siemens/ MDS or Equivelents.

(Contractor Seal & Signature)



## **EUCEE & ASSOCCIATES**

#### AR. U. C. SRIVASTAVA

"MADHAV KUNJ", MIG-169, RAPTI NAGAR PHASE-1, GORAKHPUR, U.P. MOBILE NO.- 7571000869

### DETAIL TENDER FOR FURNISHING WORK OF BARODA U.P. BANK, MOKHALISPUR BRANCH, DISTT.- SANT KABIR NAGAR.

S.NO	DADTICULAD OF WORK	OTN	TINITE	DATE	AMOUNT
	PARTICULAR OF WORK	QTY.	UNIT	RATE	AMOUNT
The state of the s	Providing and erection on site wooden computer counter as per designed. Height of counter will be 2'-6" high of writing desk will be 2'-6" deep. It should be made out of block board 19 mm. thick and 1 mm. thick laminates (as per shade approved by the color code of bank) the inside desk will be provided with 16" wide 5" high & 24" deep drawers with telescopic channel have lock of approved make. All the exposed edge of block board will be provided with 38mm. thick teak wood lapping duly melamine polished with CPU. platform at the foot rest and provision of wire manager complete in all respect.	10	RFT		
2	CASH COUNTER  Providing and erection on site wooden cash counter as per designed with two level height of counter will be 2'-6" & 4'-0"(12mm.th.eached glass) high of writing desk for the cashier will be 2'-9" deep will have key board arrangement with drawer unit. The counter top for the client will be 1'- 3" wide of 12mm.th.glass. The writing top will be made out of block board 19mm th. & 1mm th. Laminate, (shade as per color code approved by the bank.)The inside 3 nos. of drawer will provided with 16" wide, equal high & 24" deep drawers with telescopic channel have lock of approved make. All the exposed edge of block board will provided with 38 mm. th. Teak wood lapping, with melamine polish CPU. platform at the foot rest and provision of wire manager complete in all respect.	5	RFT		
3	LOW HT. PARTITION WITH WICKET GATE  & COUNTER PARTITION.  Providing and erection of partly glazed (Eached glass 12mm th. As per architect design) laminated partition / flap door with door spring up to 4'-6"	200	SFT		

1	high made out of 2"x11/2" well seasoned Kail wood					
,	with anti termite treatment under framing at 2'-0"					
	c/c in both direction covered with 6 mm th.					
	Commercial ply and 1 mm. thick laminate on both					
	side. All free top / end surface will have teak wood					
	moulds with Malamine polished. The rate of glass					
_	including.					
	CASH CABIN FRONT PARTITION (7'-0"HT.)					
	P/F of eached glasses 12mm th. In front of cash					
	counter with provision of booking cage in center &	18	SFT			
	1.5" slit at 5'-0" height from floor level. ((design as		1 1			
	per architect).as per specification of item no.2)					
	CASH CABIN SIDE PARTITION (7'-0"HT.)					
	Providing and erection of partly glazed (eached					
	glass 12mm th. As per architect design) laminated					
3	glass 12mm th. As per architect design) laminated		1 1			
	partition made out of 2"x1.5" well seasoned kail		1 1			
	wood with anti termite treatment under framing at	100	SFT			
	2'-0" c/c in both direction with provision of slit.					
	Covered with 6 mm th. Commercial ply and 1					
9	mm. thick laminates on both sides. All free top / end					
	surface will have teak wood moulds with malamine					
	polished.					
()	CASH CABIN BACK PARTITION (7'-0"HT.)					
c) .	Providing and erection of partly glazed (eached		/			
	Providing and election of party grazed (edened					
	glass 12mm th. As per architect design) laminated					
	partition made out of 2"x1.5" well seasoned kail					
	wood with anti termite treatment under framing at	35	SFT			
	2'-0" c/c in both direction with provision of slit.					
	Covered with 6 mm th. Commercial ply and 1 mm.					
	Thick laminates on both sides. All free top / end					
	surface will have teak wood moulds with		1			
	2Melamine polished.					
	ROOF ALUMINIUM GRILL FOR CASH					
	CABIN WITH BEADING AND POLISH					
DOMES .	CABIN WITH BEADING AND TOLISH	35	SFT			
(d)	TO COMPLETED	33	JI I			
,	GLASS BARIER IN FRONT OF COMPUTER					
	TABLE.					
	P/F of eached glasses 12mm th. With colored logo		20022000			
	of Baroda UP Bank in front side computer counter	25	SFT			
	with beading on frame work as per item no.2&3 and					
:::	provision of booking cage in center (design as per					
	architect).					
)	SUGGESTION BOX/ CHEQUE DROP BOX.			1		
	Providing & placing in position of suggestion box/					
	cheque drop box (size 18"x18"x6") made out of	_	<b>N</b> T			
	19mm th Board with 1mm th. Lamination on all	2	Nos.			
	exposed surface covered with teak wood lapping					
	with malamine polish. Front side 6mm th. Glass		1			
	Guing in 2" the Teak wood lanning					
	fixing in 2" th. Teak wood lapping.					
	NOTICE BOARD.					
7		1				
7	Providing and fixing of notice board 3'x2' made out	1			1	
7	of 12mm th. Cello teak board with velvet cloths	1	No.			
7	of 12mm th. Cello teak board with velvet cloths lining on it will have 1.5"x1" sal wood framing side	1	No.			
7	of 12mm th. Cello teak board with velvet cloths lining on it will have 1.5"x1" sal wood framing side will be of 19mm th. Board with 1 mm th. Laminate (as per shade approved by the architect) front will	1	No.			

	have 6mm th. Glass with sliding arrangement with locking device all complete.					
	DOOR CLOSURE ( Cash Cabin , B.M. Cabin &					
	Toilet)					
	Providing & fixing of Hydrolic door closure heavy		1			
	duty of Godrej make for door.	3	Nos.			
	NIGHT LATCH LOCK.		11031			
	Providing & fixing of Godrej made night latch locks					
	for eash cabin doors.	1	No.			
0	CAPSUL DOOR SPRING		110.			
U	P/F of Capsul door spring in low height partition					
		4	Nos.			
	door including flap door.	4	1105.			
1	DESIGNER DISPLAY BOARD IN B.M. CABIN					
	Providing and fixing pin up board of 12 MM th.	10	SFT			
	Cello teak board covered with approved fabric in	10	SFI			
	matty with Tk. Wood lapping all around and edge					
	rounded Complete with polish and melamine finish.					
12	ALUMINUM & GLASS ENTRANCE DOOR					
	WITH PROVISION OF EXHAUST FAN.					
	Made out of aluminium framing					
	1.75"x1.75"x1.5mm and door vertical, top/middle	85	SFT			
	1.75"x1.75"x1.5mm thick bottom	00	00			
	4.5"x1.75"x1.5mm with 6mm plain eached glass at					
	8'-0"ht.grill upto ceiling height as approved design					
	by bank architect.					
13	ALUMINIUM DOOR LOCK		2000			
	supply & fixing of aluminum door lock.	1	No.			
14.	FLOOR SPRING					
-3	P/F of floor spring of godrej made big size for front	2	Nos.			
	side 12mm th. Glass door					
15	6 LIVER GODREJ MORTISE LOCK IN B.M					
1.5		2	Nos.			
	CABIN	-	1103.			
16	B.M.TABLE					
	Providing and placing in position, table made of 19					
	MM, BWR, termite proof,borer proof commercial					
	finish with top, front, and sides finished in 1 MM					
	th.on one side with necessary mouldings, lippings in					
	TK. Wood. Laminate is to fixed in book matching					
	fashion, as per the design. TK. Wood sections to be					
	provided in the table as per the requirement &					
	design, storage unit will consist of drawers, and			//		
	open able shutters, keyboard drawers, space for	ii:				
	keeping C.P.U.,and suitable fascia to be provided as					
	per the design. Drawers will consist of 12 MM thk.	1	No.			
	Commercial finish ply for bottom sides & back and					
	Commercial finish provided with specified		T .			
	19 MM thk. Commercial finish board with specified					
	LAMINATE on the front side, the fascia of drawers					
	to be made empanelled fashion using 12 mm ply to	2				
	create level differences and using necessary	1				
	The second secon	)			1	
	mouldings on the tucks as per the detail. Drawers to	3				
	mouldings on the tucks as per the detail. Drawers to slide on telescopic sliding mechanism. All exposed	1				
	slide on telescopic sliding mechanism. All exposed	i				
	mouldings on the tucks as per the detail. Drawers to slide on telescopic sliding mechanism. All exposed edges of ply/ board to be finished in 3 mm thk. Tk Wood lipping. All the units to be provided with	i	C.Srivas			

	multipurpose locks (Godrej make, pais separately), sliding mechanism of magnetic catchers, brass piano hinges, PVC ferrules, etc. All hardware to approve by the Architect and to be of superior brass / S.S. finishes & lacquered. All exposed wooden surfaces to be polished in high class French spirit polish in reddish/ rosewood/ red cedar tint as per approved sample and finished in 2 coats of melamine in matt finish. All unexposed areas to be wax polished /enamel painted & wood primer with Glass Table Top full size 12mm all complete as per details in neat fashion.			
	(a) size: 6'-0" (L) x 3'-0" (W) x 2'-6" (H)			
17	REUSING OLD TABLE WITH NEW PLY AND MICA (Same as item no. 16)	1	No.	
18	SIDE & BACK CABINETS (B.M.): Providing and placing in position SIDE & BACK Cabinet made of 19 mm th. Commercial finish board with 1 mm thk. Laminate finish, along with drawers, cabinets, shelves & locks as per detail.	55	SFT	
19	CUSTOMER DESK/ WRITING DESK; Providing & fixing of customer desk made out of 19 mm. Board with 1mm th. Laminate inside and outside as per colour code and melamine polish on beading work of size 1'x4'x6" with 4 nos. of pocket fixed on wall complete in all respect.	1	No.	
	TOTAL AMOUNT:			

#### LIST OF APPROVED MATERIAL & MAKE

1. BOARD/PLY	: CENTURY, GREEN.
2. LAMINATE	: AICA SUNMICA, CENTURY
3. GLASS	: TATA FLOT GLASS, MODI, ASAHI
4.ADHESIVE	:FEVICOL, JEEVANJOR
5. LOCK / NIGHT LATCH	: GODREJ, LINK .
6.FIXTURE/FITTING	:EARL BIHARI, ELIBE
7. WALL CARE PUTTY / P.O.P.	: BIRLA, J.K. PUTTY
8. PAINT	: ASIAN, NEROLAC, BERGER
9. FLOOR SPRING	: GODERJ.

#### NOTE:

1. DETAILS OF COLOR OF LAMINATION ARE AS PER COLOR CODE OF BARODA UP BANK.

2. COLORED LOGO ON EACHED ENTRANCE GLASS DOOR B.M. CABIN DOOR, COUNTER & CASH CABIN

FRONT GLASS.

DATE: 17.01.2022

C(U.G. SKIVASTAVA)

(Contractor's Seal & Signature)

PANEL ARCHITECT

BARODA U.P. BANK