

RO/ALLA/P&E/2022-23/19

Date:- 06.07.2022

TENDER FOR ELECTRICAL WORK, LAN CABLING, FALSE CEILING & SIDE UNITS OF REGIONAL OFFICE ALLAHABAD

Baroda UP Bank Regional Office Allahabad, 3 D Tashkant Marg Civil Line, invites sealed tender for furnishing for our **Regional Office** (Dist- Prayagraj) from the empanelled Furnishers of Baroda UP Bank, Head Office, Buddh Vihar Taramandal Gorakhpur-273016 (U.P).

- | | |
|---------------------------------------|---|
| 1. Tender issuing date | : 06.07.2022 |
| 2. Last date for submission of tender | : 21.07.2022 at 3:00 PM |
| 3. Date of opening of tender | : 22.07.2022 at 3.00 PM |
| 4. Contact Number | : 7839884103 |
| 5. Tender to be address to | The Regional Manager Baroda UP Bank, Regional Office- Allahabad, 3D Tashkant Marg Civil Line; 211001 |

Terms and condition of tender:

- Ø Rates should be quoted on the space provided in **annexure attached only**. No other sheet/form should be used for quoting rates.
- Ø The competent authority (bank) does not bind themselves to accept the lowest or to give any reasons for its decision of acceptance or rejection of tenders.
- Ø Incomplete in any respect or conditional tender shall liable to be rejected.
- Ø Rates quoted only by bank's empanelled vendors will be consider/accepted.

Other conditions:

- Ø The registration number of the firm along with **GST no.** allotted by the authorities must be submitted.
- Ø **PAN NUMBER** of the firm allotted by the income tax authorities should be submitted (without which the vendor's bid would become invalid and shall be liable to reject)
- Ø Conditional tenders shall not be accepted on any ground and shall be rejected straight.
- Ø Any deviation of the conditions given by the purchaser will not be accepted and bid will be rejected without assigning any reasons.
- Ø If any clarification is required the same should be obtained before submitting the bid.

- Ø The entire document must be signed with the seal and attached as mark of acceptance of terms and condition.
- Ø BUPB reserve the right to accept or reject any bid whole or in parts without assigning any reason thereof.
- Ø Bank's decision will be final and no correspondence will be entertained in this regard.
- Ø In case of delays in submission/non submission of bids ,Bank will not assume any responsibility.
- Ø Bank may reject any or all quotations without assigning any reason.

Tender submission:

Submission of tenders in sealed envelope super scribing "TENDER OF FURNISHING OF REGIONAL OFFICE ALLAHABAD" addressed to "The Regional Manager Baroda UP Bank, Regional Office-Allahabad, 3D Tashkant Marg Civil Line; 211001", Complete in all respect latest by 3.00 PM dated-21.07.2022 Tenders received after that shall not be entertained.

Tender must be submitted through hand to hand or through registered post.


Evaluation of tender:

Quoting incredibly low value of items with a view of subverting the tender process shall be rejected straight away.

Yours faithfully,



(Soran Singh)
Regional Manager



Detail Tender for Electrical work LAN Cabling Work & False Ceiling + Side Units of Regional Office Prayagraj

| Sl. No. | Particulars | Qty. | Unit | Rate/Unit | | Amount | |
|---------|--|------|------|-----------|----|--------|----|
| | | | | Rs. | P. | Rs. | P. |
| 1. | S/F of plug socket board consisting of 3 plug 5 Amp, three pin, three switch and one indicator with 1.5 sq mm separate circuit wiring for computer . | 28 | No | | | | |
| 2. | S/F of UPS earthing-S/burying of Dual pipe technology (Pipe in Pipe) earthing electrode having GI 80mm O/D pipe with 25 micron coating, 3metres long. The space between two pipes to be filled with Highly conducive & Non corrosive chemical compound. The vacant space between pipe & hole shall also be filled with Compound all around. The job also includes S/F of GI strip clamp with two holes (with SS/GI bolts & nuts) on the electrode& taking two earthing leads of 4mm dia copper wire (Assumed length of 10m -beyond 10m to be paid extra) upto Main panel complete in all respects with guaranteed E/N voltage of less than 2 volts and resistance less tahn 1ohms. The 4mm dia Cu. earth wire shall be terminated on a separate 6way earthlink. The connections for Panel earthing& earth bus in the panle should be taken from this earthlink | 3 | No | | | | |
| 3. | Supplying and fixing recessed mounting fittings with suitable for 35/40 watt LED 600x600 Square fitting with PDC Aluminum die cast housing with poly Corbonet diffuser, in built electrical 110 LM Per watt protection like over voltage, short circuit, over loading, mis wiring for additional safety precaution rated light 50000 hours, (Guaranteed for above LED light is three month from period of installation) Make Crompton Cat No. LCTLRNE-36-FO-CDL,LED 36W or Philips make Model No. 380 LED 42S DN (38 W) Wipro Cat- Garnet Slim LED D414065 (All complete with Lamps | 36 | No | | | | |

| | | | | | |
|-----|---|----|----|--|--|
| 4. | S/W 10 Amp, Plug point with 2.5 sq mm copper wire in counter with continuous earthing wire complete in all respect with modular switches /socket. | 24 | No | | |
| 5. | S/F of LED Batten 20 watt light Fitting with 1.5 sq mm wiring complete in all respect including modular switches | 10 | No | | |
| 6. | S/F of 20 Amp plug point with 2.5 sq mm wiring including modular switches /socket with continuous circuit wiring. | 20 | No | | |
| 7. | Supplying and fixing 4 WAY TPN DB Double door 1p43 With 10-32 amp SP MCB 10 KA & 63 AMP 4 POLE MCB For A.C | 04 | No | | |
| 8. | Providing & Fixing of wall fans & point complete with 1.5 Sq mm wiring and modular switches. | 30 | No | | |
| 09. | Supplying and fixing of Call Bell in BM's cabin including wiring etc. | 02 | No | | |
| 10. | Supplying and Fixing of cabin fans (400Dia) in cash cabin/ in 1.5 sq mm wiring and modular switches. | 0 | No | | |
| 11. | Supplying and Fixing of circuit wiring for computer in 2.5 sq mm copper wire. | 20 | No | | |
| 12. | Supplying and Fixing of wiring for lights and fans 1.5 sq mm copper wire complete in all respect. | 20 | No | | |

| | | | | | |
|-----|--|----|-----|--|--|
| 13. | Supplying and Fixing recessed mounting fittings with suitable for 18/20 Watt LED down Light fitting with PDC Aluminium diecast housing with Poly Carbonate diffuser, in built electrical protection like over voltage, short circuit, over loading, mis wiring for additional safety precaution rated light 50000 hours, (Guaranteed for above LED light is three month from period of installation) Philips make DN195BLED 20F (20 WATT) 6500 KA < Crompton Cat No. LCBE18 – CDL- 18 Watt & Wipro cat- Gernet slim D7112060/40/30 6500 KA (complete with all) | 30 | No | | |
| 14. | S/F of A.C. point wiring with 2x 4 sq mm+1x1.5 sq mm copper wire and metal socket MCB 20 Amp. complete For 1.5 Ton/ | 16 | No | | |
| 15. | Supplying and Fixing of exhaust fan in toilet/hall 15 Inch dia 1.5 sq mm wiring and modular switches. | 2 | No | | |
| 16. | S/F of ceiling fan (1200 dia) with hooks in rooms with adding rod of suitable length wherever necessary including 1.5 sq mm wiring and modular switches and regulator | 2 | No | | |
| 17. | S & F of 12 way SPN DB double door with 10No SP MCB and 1 no DPMCB 40 AMP for computer | 6 | No | | |
| 18. | Sub main wiring of UPS input and UPS output power supply with 2 no 6 sq mm No. 4 sq mm copper flexible wire in PVC conduit pipe. (payment as/actual length on site) | 70 | Mtr | | |

| | | | | | |
|--------------------|--|------|------|--|--|
| 19. | Sub main wiring of power supply from Main to TPN distribution Board with 4 nos 10 sq mm copper flexible wire and 1 no 6 sq mm earth wire in PVC conduit pipe. (payment as/actual length onsite) | 70 | Mtr | | |
| 20. | Supplying / Fabricating / installation of Panel Board made of 16 gauge CRC sheet 415 V Incoming: TPN MCCB 250 Amp _1 No 36 KA (4 pole) Out going 100 Amp MCCB 4 pole -3 no 250 Amp Change Over 4 pole _ 1 No 63 Amp Change Over for ups _ 1 no and 63 Amp 4 Pole MCB - 1 no With Double Bus Bar Chamber Complete with metering system | 1 | Set | | |
| 21. | Supply and fixing on board 3 no KIT KAT cut out 200 amp with neutral link on board | 1 | Job | | |
| 22. | S/F of ceiling fans (1200 dia) with hooks in rooms with adding rod of suitable length wherever necessary including 1.5 sq mm wiring and modular switches and regulator | 0 | No | | |
| LAN Cabling | | | | | |
| 23. | Supplying and drawing CAT 6 PVC insulated and Sheathed LAN cable through PVC conduit including testing, commissioning etc.as required. | 1850 | Mtr | | |
| 24. | Supply and fixing of RJ modem Jack for computer including making connection, soldering etc | 35 | No | | |
| 25. | Supply and Fixing of Patch Card with CAT 6 Jack | 35 | No | | |
| 26. | False Ceiling (Armstrong) Providing and fixing in position false ceiling in armstrong 600 x 600 x 15/16 mm dune supreme RH 99 prima tile with regular edge frame work as specified by Armstrong company with suspenders making necessary frame work for A.C. Ducting for diffusers and light fitting. | 2500 | Sft. | | |
| 27. | False Ceiling (Gypsum) Providing & fixing with necessary scaffolding frame in 22 gauge GI channel/angle, placed at appropriate grid, fixed to RCC slab, beam, wall etc. with fasteners/screws finished with 12. 0mm Gypsum sheets joints covered with | 1500 | Sft. | | |

| | | | | | |
|-----|---|------|-----|------------------|--|
| | POP slurry/tape. Rates shall include painting (One Coat of putty, one coat of primer coat and tow coats of acrylic paints.) Rates shall include providing necessary cut-outs & additional support frames for electrical fixtures, A.C. grills, vertical drop up to 1'6" etc. item includes finishing with painting base work and finishing in plastic paint of white colour. (Note:- No extra payment shall be given for design. However, the visible area of the vertical side at the intersection of Gypsum & Armstrong False ceiling shall be paid.) | | | | |
| 28. | Providing and Fixing in position side units Made out of 19mm board with 1.0 mm Laminate with slidding hinged shutters (made out of 12mm thick ply with 1.0 mm Thick laminate on it) complete with handles Etc. Size 4'-0" x 1'-6" x 2'-6" | 28.0 | No. | | |
| | | | | Total Rs. | |

GST18% -----

GRAND TOTAL -----

(Rs. ----- Lacs ----- Thousand ----- Hundred Only.)

PROJECT - SPECIFICATION FOR FURNITURE & ELECTRICAL WORKS.**BANK - BARODA U.P. BANK****REGIONAL OFFICE- PRAYAGRAJ*****ALL WORKS TO BE DONE AS PER TENDER CONDITIONS.**

| A | FURNITURE ITEMS | |
|----------|---|---|
| 1 | LAMINATES (IS-2046) / VENEER | GREEN LAM / CENTURY / ARCHID / SAMRAT / FORMICA / SUNDEK OR APPROVED EQUIVALENT |
| 2 | COMMERCIAL PLY (IS-303) / WATERPROOF PLY (IS-710) / BLOCK BOARD (IS-1659) / FLUSH DOOR (IS- 2202) | ARCHID/ SAMRAT / CENTURY / EURO / GREEN OR APPROVED EQUIVALENT BY EIC. |
| 3 | ADHESIVES | FEVICOL / BLUECOAT/ VAMICOAL |
| 4 | LOCKS | GODREJ |
| | MULTIPURPOSE GROUP LOCK | E-MPL1-22 / E-MPL1C-22 (EBCO) |
| | NIGHT LATCH | 8812 (GODREJ) |
| | CYLINDRICAL LOCK (SS MATT FINISH) | 3792-WITH KEY AND 3786-KEYLESS (GODREJ) / C120SS (EUROPA) |
| | MORTISE DEAD LOCK (TWO WAY) | 8815(GODREJ) |
| | MORTISE LOCK WITH DOOR HANDLE | MATIZ 8083(GODREJ) |
| 5 | DRAWER CHANNELS | GODREJ/ HATTICH/ OZONE |
| | TELESCOPIC CHANNELS (ZINK PLATED) | STDS35(I)35/ STDS25(I)35/ STDS50(I)35/ STDS60(I)35 (EBCO) |
| | BOTTOM CHANNELS (POWDER COATED) | BMDS 35/ BMDS 37/ BMDS 55/ BMDS 60 (EBCO) |
| 6 | GENERAL HARDWARE | SS MATT FINISH |
| | DOOR STOPPER | I) BLACK/IVORY/BROWN/SILVER COLOR POWDER COATED DS1 (EBCO) II) SPRING TYPE BLACK/BROWN/IVORY COLOR POWDER COATED (ECGL'S STERLING) |
| | HINGES | I) 3"/4"/5"/6" 1.8MM TH. SS MATT FINISH (SUZU) II) 75X12X19 1.2 MM TH. SS MATT FINISH FOR STORAGE (SUZU) III) AUTO CLOSE HINGES – SLIP ON HINGE- EURO / CLICK ON HINGE-I (EBCO) FOR STORAGE |
| | HANDLES 'D' OR 'C' TYPE | 1) 3"/4"/6"10MM DIA SS 202 MATT FINISH (ANJALI) |
| | TOWER BOLT | 3"/4"/6"/8" BRASS EXTRUDED SS MATT FINISH (OSWAL) |

| | | |
|----------|---|---|
| | SLIDING CHANNEL | EBCO MAKE APPROVED BY ARCHITEC/BANK. |
| 7 | FLOOR SPRING | |
| | 60 KG | 7477 (GODREJ) / M-74 (HARDWYN) |
| | 80 KG | 8293 (GODREJ) / M-74 (HARDWYN) |
| | 100 KG | 8294 (GODREJ) / M-76 (HARDWYN) |
| 8 | DOOR CLOSER | |
| | 60 KG | DOUBLE SPEED 8292-SILVER, 7325- GOLDEN (GODREJ) / SCORPIO (HARDWYN) |
| | FIRE RATED 60 KG | 1938 (GODREJ) / TRITON (HARDWYN) |
| 9 | PATCH FITTINGS FOR DOOR AND FIXED GLASS PARTITION (TOP/BOTTOM PATCH, PIVOT, PATCH LOCK, L ARM, L CONNECT, CONNECTOR, FLOOR SPRING, HANDLE, PLASTIC PROFILE) | GODREJ / XL C SERIES(DORMA) / OPF SERIES (OZONE) OR APPROVED EQUIVALENT |
| 10 | GLASS / MIRRORS | SAINT GOBAIN / MODI |
| 11 | ALUMINUM SECTION | JINDAL / INDAL / BANCO |
| 12 | WINDOW BLINDS | VISTA / AEROLUX/HUNTER DUGLUS / MAC |
| 13 | POLISH / PAINT | ASIAN PAINTS / BERGER / NEROLAC |
| 14 | PARTICLE BOARDS | NOVAPAN / DECO BOARD |
| 15 | COMPUTER ACCESSORIES | |
| | CPU HANGER/ SHELF | SIDE MOUNTED IS CPU HL SM (INNOFIT) /CPUSM(EBCO) , |
| | CABLE MANAGER (60MM) | I) METAL - CO60ZN1(EBCO) II) PVC - CO 60 (EBCO) BLACK/IVORY/GREY COLOR |
| 16 | ACP PANEL | TIMEX / ALU DECOR / EURO OR APPROVED EQUIVALENT |
| 19 | WHITE FILM FOR GLASS | CRYSTAL / SONA MAKE VINYL FROSTED FILM |
| | | |
| B | PAINTS | ICI, ASIAN,DULUX, BERGER, NEROLAC, JOHONSON & NICOLSAN |
| 1 | ANTI CORROSIVE PAINT | TIKITAR, FINCOAT |
| 2 | RED OXIDE | ASIAN, DULUX,NEROLAC |
| 3 | POLISH | ASIAN MELAMINE |
| 4 | EXTERIOR PAINTS | DULUX WEATHERSHIELD OR APP. EQUIVALENT |
| 5 | ENAMEL PAINT | ICI, DULUX, ASIAN, NEROLAC |
| | | |
| C | FALSE CEILING | |
| 1 | GYPSUM BOARD | GYPROC (SAINT GOBAIN) |
| 2 | FRAMING WITH COMPLETE SYSTEM | GYP STEEL ULTRA (SAINT GOBAIN), RAMCO FUJI |
| 3 | HILUX BOARDS | RAMCO OR APPROVED EQUIVALENT |

| | | |
|----------|--|--|
| 4 | MINERAL FIBRE TILES CEILING WITH COMPLETE SYSTEM | ARMSTRONG/SAINT GOBAIN/USG |
| | | |
| D | APPROVE MAKE LIST FOR ELECTRICAL | |
| | | |
| 1 | PVC rigid conduits & Accessories: | 1.5 mm thick (MMS) ISI and FIA approved - Precision / Vraj / Nihir / BLP / PFI / Anchor / Polycab make. (Only white coloured pipes FRLS type to be used.). |
| 2 | L.T. Cables: | Havells / KEI / Polycab / R. R. Kable / Finolex. |
| 3 | Wires (FRLS): | Havells / KEI / Polycab / R. R. Kable / Finolex. |
| 4 | Main Distribution Boards: | MDS Legrand (Lexic) / Hager / Crabtree XPOA / Schneider (Eazy 9) / L & T EXORA / C & S Wintrip / Siemens Bitaguard. |
| 5 | ELCB / RCCB / Miniature Circuit Breaker: | MDS Legrand (Lexic) / Hager / Crabtree XPOA / Schneider (Eazy 9) / L & T EXORA / C & S Wintrip / Siemens Bitaguard. |
| 6 | Switch gears: | MDS Legrand (Lexic) / Hager / Crabtree XPOA / Schneider (Eazy 9) / L & T EXORA / C & S Wintrip / Siemens Bitaguard. |
| 7 | Change Over Switch: | HPL Socomac/ Havells / L & T / Hager. |
| 8 | Domestic fittings: | |
| | a) All Switching Modular Accessories. | MK Wrapped Wround Plus / Schneider Livia / L & T entis / Crabtree Verona / Salzer Elite / Legrand Myris / C & S Divino / SSK Ace. |
| | b) Holders / ceiling roses | Anchor or equivalent approved make. |
| | c) Adhesive Tape | Bhor (Steel Grip) or approved . |
| 9 | 10 - 30 A Polycarbonate Socket & Top: | MDS Legrand (Lexic) / Hager / Crabtree XPOA / Schneider (Eazy 9) / L & T EXORA / C & S Wintrip / Siemens Bitaguard. |
| 10 | Telephone Wires / Cable: | Finolex / R. R. Kable / Havells / L & T / Polycab. |
| 11 | Telephone tag block: | Krone make. |
| 12 | Cable Lugs: | Dowell / Lotus / Jainson / 3 D. |
| 13 | Cable gland Single / Double Compression: | HMI / Comet / 3D. |
| 14 | Ammeter / Voltmeter: | AE / HPL / MECO / Enercon make. |
| 15 | Selector switches: | L & T salzer / Kaycee make. |
| 16 | Indicator lamps: | LED type Teknic / Precifine/ Binay. |
| 17 | Connector strips: | Wago / Elmex make. |
| 18 | Lighting Fixtures : | Wipro / Philips / GE / Crompton. only |
| 19 | Exhaust fan (Light duty): | Khaitan / Crompton / Havells. |
| 20 | Ceiling Fan (5 star rated): | Crompton (High Breeze Plus) / Havells. |
| 21 | Wall mounted Fan (5 star rated): | Crompton (High Flow Wave) / Havells. |

