



बड़ौदा यू.पी. बैंक Baroda U.P. Bank

FULL DETAIL OF TENDER

| क्रमांक | विवरण | |
|---------|---|--|
| 01 | निविदा शुरू होने की तिथि | 03.09.2022 |
| 02 | निविदा खत्म होने की तिथि | 10.09.2022 |
| 03 | निविदा में भागीदारी हेतु निविदा राशि | फर्निशिंग हेतु रू 5000/- का बैंक ड्राफ्ट/सावधि जमा पत्र एवं नेटवर्किंग/इलेक्ट्रिक वर्क्स हेतु रू 3000/- का बैंक ड्राफ्ट/सावधि जमा पत्र |
| 04 | प्रतिभूति स्वरूप राशि | कुल बिल राशि का 10 % |
| 05 | प्रतिभूति का स्वरूप | सावधि जमा पत्र/बैंक ड्राफ्ट |
| 06 | क्षेत्रीय कार्यालय को निविदा प्राप्त होने की अंतिम तिथि | 12.09.2022 सायं 5:00 |
| 07 | निविदा खुलने की तिथि | 13.09.2022 |
| 08 | कार्य समाप्ति की अंतिम तिथि | 22.09.2022 |

नोट:-

- फर्निशिंग एवं नेटवर्किंग/इलेक्ट्रिक का टेंडर अलग-अलग सीलड पैक लिफाफे में भेजे जिसके ऊपर " टेंडर-फर्निशिंग " / " टेंडर-नेटवर्किंग/इलेक्ट्रिक " अवश्य लिखे ।
- टेंडर भेजने का पता :- क्षेत्रीय प्रमुख , बड़ौदा यू.पी.बैंक, क्षेत्रीय कार्यालय, कुबेर स्थान रोड , छावनी , पडरौना , जिला कुशीनगर , उ.प्र., पिन -274304
- बैंक ड्राफ्ट /सावधि जमा पत्र क्षेत्रीय प्रमुख , बड़ौदा यू.पी. बैंक , क्षेत्रीय कार्यालय पडरौना के पक्ष में बंधक होगा ।
- किसी भी दशा में निविदा के अंतिम तिथि के पश्चात निविदा स्वीकार नहीं किया जाएगा ।
- सफल प्रतिभागी द्वारा कार्य कराने के पश्चात बिल राशि का 10% प्रतिभूति स्वरूप रखा जाएगा जिसे कार्य समाप्ति के एक वर्ष के पश्चात मांग करने पर वापस किया जाएगा ।
- बैंक के पैत्रल में सम्मिलित टेंडर ही निविदा में शामिल हों ।

Regional Head
Baroda Up Bank, Padrauna

(A)



बड़ौदा यू.पी. बैंक Baroda U.P. Bank

DETAIL ESTIMATE FOR FURNISHING WORK OF BARODA U.P. BANK, BARWARATANPUR BRANCH, DISTT.-KUSHINAGAR.

| S.NO | PARTICULAR OF WORK | QT Y. | UNI T | RAT E | AMOU NT |
|-------|--|----------|----------|----------|------------|
| 1 | <u>COMPUTER COUNTER</u> Providing and erection on site wooden computer counter as per designed. Height of counter will be 2'-6" high of writing desk will be 2'-6" deep. It should be made out of block board 19 mm. thick and 1 mm. thick laminates (as per shade approved by the color code of bank) the inside desk will be provided with 16" wide 5" high & 24" deep drawers with telescopic channel have lock of approved make. All the exposed edge of block board will be provided with 38mm. thick teak wood lapping duly melamine polished with CPU. platform at the foot rest and provision of wire manager complete in all respect. | 10 | RFT | | |
| 2 | <u>CASH COUNTER</u> Providing and erection on site wooden cash counter as per designed with two level height of counter will be 2'-6" & 4'-0"(12mm.th.eached glass) high of writing desk for the cashier will be 2'-9" deep will have key board arrangement with drawer unit. The counter top for the client will be 1'-3" wide of 12mm.th.glass. The writing top will be made out of block board 19mm th. & 1mm th. Laminate, (shade as per color code approved by the bank.)The inside 3 nos. of drawer will provided with 16" wide, equal high & 24" deep drawers with telescopic channel have lock of approved make. All the exposed edge of block board will provided with 38 mm. th. Teak wood lapping, with melamine polish CPU. platform at the foot rest and provision of wire manager complete in all respect. | 10 | RFT | | |
| 3 | <u>LOW HT. PARTITION WITH WICKET GATE & COUNTER PARTITION.</u> Providing and erection of partly glazed (Eached glass 12mm th. As per architect design) laminated partition / flap door with door spring up to 4'-6" high made out of 2"x1 1/2" well seasoned Kail wood with anti termite treatment under framing at 2'-0" c/c in both direction covered with 6 mm th. Commercial ply and 1 mm. thick laminate on both side. All free top / end surface will have teak wood moulds with Malamine polished. The rate of glass including. | 60 | SFT | | |
| 4 (a) | <u>CASH CABIN FRONT PARTITION (7'-0"HT.)</u> P/F of eached glasses 12mm th. In front of cash counter with provision of booking cage in center & 1.5" slit at 5'-0" height from floor level. ((design as per architect).as per specification of item no.2) | 33 | SFT | | |
| (b) | <u>CASH CABIN SIDE PARTITION (7'-0"HT.)</u> Providing and erection of partly glazed (eached glass 12mm th. As per architect design) laminated partition made out of 2"x1.5" well seasoned kail wood with anti termite treatment under framing at 2'-0" c/c in both direction with provision of slit. Covered with 6 mm th. Commercial ply and 1 mm. thick laminates on both sides. All free top / end surface will have teak wood moulds with malamine polished. | 150 | SFT | | |



बड़ौदा यू.पी. बैंक Baroda U.P. Bank

| | | | | | |
|-----|---|-----|------|--|--|
| (c) | CASH CABIN BACK PARTITION (7'-0"HT.) Providing and erection of partly glazed (eached glass 12mm th. As per architect design) laminated partition made out of 2"x1.5" well seasoned kail wood with anti termite treatment under framing at 2'-0" c/c in both direction with provision of slit. Covered with 6 mm th. Commercial ply and 1 mm. Thick laminates on both sides. All free top / end surface will have teak wood moulds with 2 Melamine polished. | 70 | SFT | | |
| (d) | ROOF ALUMINIUM GRILL FOR CASH CABIN WITH BEADING AND POLISH | 70 | SFT | | |
| 5 | GLASS BARIER IN FRONT OF COMPUTER TABLE. P/F of eached glasses 12mm th. With colored logo of Baroda UP Bank in front side computer counter with beading on frame work as per item no.2&3 and provision of booking cage in center (design as per architect). | 20 | SFT | | |
| 6 | SUGGESTION BOX/ CHEQUE DROP BOX. Providing & placing in position of suggestion box/ cheque drop box (size 18"x18"x6") made out of 19mm th. Board with 1mm th. Lamination on all exposed surface covered with teak wood lapping with malamine polish. Front side 6mm th. Glass fixing in 2" th. Teak wood lapping. | 2 | Nos. | | |
| 7 | NOTICE BOARD. Providing and fixing of notice board 3'x2' made out of 12mm th. Cello teak board with velvet cloths lining on it will have 1.5"x1" sal wood framing side will be of 19mm th. Board with 1 mm th. Laminate (as per shade approved by the architect) front will have 6mm th. Glass with sliding arrangement with locking device all complete. | 1 | No. | | |
| 8 | DOOR CLOSURE (Cash Cabin , B.M. Cabin) Providing & fixing of Hydraulic door closure heavy duty of Godrej make for door. | 6 | Nos. | | |
| 9 | NIGHT LATCH LOCK. Providing & fixing of Godrej made night latch locks for cash cabin doors. | 2 | Nos. | | |
| 10 | CAPSUL DOOR SPRING P/F of Capsul door spring in low height partition door including flap door. | 1 | No. | | |
| 11 | DESIGNER DISPLAY BOARD IN B.M. CABIN Providing and fixing pin up board of 12 MM th. Cello teak board covered with approved fabric in matty with Tk. Wood lapping all around and edge rounded Complete with polish and melamine finish. | 10 | SFT | | |
| 12 | ALUMINUM & GLASS ENTRANCE DOOR WITH PROVISION OF EXHAUST FAN. Made out of aluminium framing 1.75"x1.75"x1.5mm and door vertical, top/middle 1.75"x1.75"x1.5mm thick bottom 4.5"x1.75"x1.5mm with 6mm plain eached glass at 8'-0"ht.grill upto ceiling height as approved design by bank architect. | 100 | SFT | | |
| 13 | ALUMINIUM DOOR LOCK supply & fixing of aluminum door lock. | 1 | No. | | |



बड़ौदा यू.पी. बैंक Baroda U.P. Bank

| | | | | | |
|----------------------|---|-----|------|--|--|
| 14 | FLOOR SPRING P/F of floor spring of godrej made big size for front side 12mm th. Glass door | 2 | Nos. | | |
| 15 | 6 LIVER GODREJ MORTISE LOCK IN B.M CABIN | 4 | Nos. | | |
| 16 | REUSING OLD TABLE WITH NEW PLY AND MICA Same as item no. 16 | 1 | No. | | |
| 17 | SIDE & BACK CABINETS : Providing and placing in position SIDE & BACK Cabinet made of 19 mm th. Commercial finish board with 1 mm thk. Laminate finish, along with drawers, cabinets, shelves & locks as per detail. | 10 | SFT | | |
| 18 | CUSTOMER DESK/ WRITING DESK: Providing & fixing of customer desk made out of 19 mm. Board with 1mm th. Laminate inside and outside as per colour code and melamine polish on beading work of size 1'x4'x6" with 4 nos. of pocket fixed on wall complete in all respect. | 1 | No. | | |
| 19 | FULL HT. PARTITION. Providing and erection of partly glazed (Eached glass 12mm th. As per architect design) laminated partition / flap door with door spring up to 8'-0" high made out of 2"x1 1/2" well seasoned Kail wood with anti termite treatment under framing at 2'-0" c/c in both direction covered with 6 mm th. Commercial ply and 1 mm. thick laminate on both side. All free top / end surface will have teak wood moulds with Malamine polished. The rate of glass including. | 300 | SFT | | |
| 20 | PILLAR PANELING Providing and Fixing of frame work on Pillars with Ply & Mica as per Partition Given above with same colour code complete in all respect upto ceiling height. | 60 | SFT | | |
| TOTAL AMOUNT: | | | | | |

LIST OF APPROVED MATERIAL & MAKE

| | |
|-----------------------------|---|
| 1. BOARD/PLY | :CENTURY, GREEN. |
| 2. LAMINATE | :AICA SUNMICA, CENTURY |
| 3. GLASS | :TATA FLOT GLASS, MODI, ASAHI |
| 4. ADHESIVE | :FEVICOL, JEEVANJOR |
| 5. LOCK / NIGHT LATCH | : GODREJ, LINK . |
| 6. FIXTURE/FITTING | :EARL BIHARI, ELIBE |
| 7. WALL CARE PUTTY / P.O.P. | : BIRLA, J.K. PUTTY |
| 8. PAINT | : ASIAN(Plastic Pant), NEROLAC (Plastic Pant) |
| 9. FLOOR SPRING | : GODERJ. |

NOTE:

1. DETAILS OF COLOR OF LAMINATION ARE AS PER COLOR CODE OF **BARODA UP BANK**.
2. **COLORED LOGO** ON EACHED ENTRANCE GLASS DOOR B.M. CABIN DOOR, COUNTER & CASH CABIN FRONT GLASS.

Regional Head
Baroda Up Bank, Padrauna



बड़ौदा यू.पी. बैंक Baroda U.P. Bank

SPECIFICATION FOR ELECTRICAL WIRING & DATA CABLING WORK FOR BARODA UP BANK AT BARWA RATANPUR BRANCH, KUSHINAGAR.

| S.No. | Description of Items | Qty. | Unit | Rate | Amount |
|-------|---|------|------|------|--------|
| 1- | Supply & Fixing of FP MCCB 100Amp 25ka with Enclosure near Energy Meter before Electricity Mains. | 1 | Set. | | |
| 2- | Fuse Grip (Cut-out): Supply & Fixing of Kit-Kat Fuse Unit 100Amp three phase and Neutral set. | 1 | Set. | | |
| 3 | On Load Changeover: Supply & Fixing of Four Pole Changeover Switch 100A 240Volt. | 1 | No. | | |
| 4 | Bus-Bar: Supply & Fixing of Copper Bus-Bar Unit 100A for Light/Fan, Power, UPS & AC distribution. | 1 | No. | | |
| 5 | Supply & Fixing of SPN MCB DB 12way Double Door with 40Amp DP RCCB 300ma for Light/Fan, UPS & Power. | 4 | No. | | |
| 6 | Supply & Drawing Circuit line by (2x6+1x4.0)Sq.mm FRLS Copper Wire for Mains Connections. | 20 | Mtr. | | |
| 7 | Supply & Drawing Circuit line by (2x4+1x2.5)Sq.mm FRLS Copper Wire for UPS, SPNDB. | 60 | Mtr. | | |
| 8 | Supply & Drawing Circuit line by (2x2.5+1x1)Sq.mm FRLS Copper Wire for All Circuit wiring. | 100 | Mtr. | | |
| 9 | Supply & Drawing Circuit line by (2x1.5+1x1)Sq.mm FRLS Copper Wire for PC Circuit wiring. | 150 | Mtr. | | |
| 10 | Supply & Fixing for Raw Power 6/16Amp Socket with Switch. | 4 | No. | | |
| 11 | Supply & Fixing for PC Terminal Power Board 4way 6Amp Socket with Switch. | 8 | No. | | |
| 12 | Supply & Fixing Power Box with 20Amp SPN MCB and including Power Top for Safe & Stationary Circuit. | 2 | No. | | |
| 13 | Supply & Laying 10Sq.mm Copper/GI Strip Wire for Earthing Circuit Earth Place to UPS & Main. | 60 | Mtr. | | |
| 14 | Supply & Drawing LAN Cabling by CAT-6 in PVC Conduit Pipe. | 200 | Mtr. | | |
| 15 | Supply & Fixing Data 9U Rack as per advice by Bank Authority complete in all respects. | 1 | No. | | |
| 16 | Supply & Fixing Networking Information Outlet Box with RJ-45 connector complete in all respects. | 8 | No. | | |
| 17 | Earthing Work: Supply & Fixing Maintenance Free Pipe Earth 80mm with Backfil compound 40kg Bag resistance should be less than 2.0 Ohms specification as per IS 3043/1987 complete in all respects. | 2 | No. | | |
| 18 | Supply & Fixing 40/32Amp DP MCB with Enclosure for UPS Incoming. | 1 | Set. | | |
| 19 | Supply & Fixing 25Amp DP MCB with Enclosure for UPS Outgoing. | 1 | Set. | | |

| | | | |
|----|---|--------|------|
| 18 | Supply & Fixing 40/32Amp DP MCB with Enclosure for UPS Incoming. | 1 Set. | 0.00 |
| 19 | Supply & Fixing 25Amp DP MCB with Enclosure for UPS Outgoing. | 1 Set. | 0.00 |

0.00

List of Approved Make:-

| | |
|---------------------------------------|--|
| Copper Wire FRLS Grade Electric Cable | : Finolex/ Polycab/ Havell's/ HCL/ Anchor/ RR Kable. |
| ELCB, MCCB & RCCB | : Havell's/ Polycab/ Kent/ SSK or Equivelent. |
| MCBs, DBs, SFUs | : L&T/ Indo-asian/ Havell's/ ABB/ HPL/ Leagrand. |
| Modular Switch, Sockets | : L&T/ Indo-asian/ Havell's/ ABB/ HPL/ Leagrand. |
| Earthing for Bldg. & UPS | : Anchor /Roma/ Crabtree/ MK/ Polycab/ Leagrand. |
| PVC Conduit Pipe | : Earth Electrode IS:3043-1978 Chemical Earthing. |
| Telephone & Data Cable | : AKG/ Precision/ Polycab/ Asian/ Fonolax. |
| Lugs | : D-link/ Finolex/ Polycab/ V-Gaurd/ HCL/ RR Kable. |
| Metal Clad Sockets | : Dowells/ Jainson or Equivelents. |
| | : HPL/ ABB/ Indo-asian or Equivelents. |

Regional Head

(A)

[Handwritten signature]