

Gunjan and Associates
Architects, Engineers, Interiors
& Landscape Designers

141, Sainik Nagar, Raebareilly Road, Lucknow-226002

Phone: 0522-3553324, 9839018489, 9838818489

E-mail:studio@gunjanandassociates.com

URL:www.gunjanandassociates.com

Bill of Quantitiy for Furnishing & Electrical works for Baroda U.P. Bank

at Meeting Room, Regional Office Faizabad

1.No offsite prefabrication shall be allowed in any case. All fabrication shall be done at the site after getting the materials inspected by the architect

2.No payment shall be made for any in completed or unsatisfactory work

3.List of material to be strictly as per the booklet.

4.All underframe should be properly treated with antitermite and waterproofing material

S.No.	Item	Units	Qty.	Rate	Amount
1	CONFERENCE TABLE (as per design)	Rft	45.00		
	Providing and fixing in position conferrence Table of size as per drawing complete in all respects made of 19 mm commercial board BWP laminated with 1 mm thick laminate all exposed edges of table top & ply verticals to have 1"x1/4" T.W. lipping. All exposed T.W. sections to be melamined and internal Surfaces to have white enamel paint / Liner laminate as directed. Item to include plywood boxing, all necessary hardware and fittings in Stainless Steel finish, lipping to all edges etc. complete in all respects.				
2	Vertical Blinds	Sqft	44.00		
	Providing & fixing MARVEL/Vista make as approved by Bank's Engineer/Architect with runner, thread and other accessories				
3	Wall Pannelling	Sqft	750.00		
	Wall Panelling-upto false ceiling height only considered and above necessary ceiling supports shall be provided) with Anodized Aluminium frame work, heavy sections (2mm thickness) of 2"x1.5", spacing of 2'0"x2'0" on bothsides and covered with 9mm thick BWP plywood finished with 1mm thick laminate colours for skirting & borders,. Rate to include providing cutouts and provisions to run electrical conduits, switches, etc. Cost include necessary hardwares like clamps, screws and etc. Cost include provisions for electrical db closing 19mm BWP plywood door arrangements, wastages, transports, loading, unloading charges, labours, materials, tools, ead, lift and etc. Complete as per drawings and instructions of the Architect.				
4	Vitrified Tile Flooring	Sqft	400.00		
	Removal of existing flooring and Providing and laying of 2' x 2' Vitrified tile flooring of approved make & shade viz.RAK (IMP- OFGY) or EURO (ATHENA) or similar make over necessary leveling Screed of 1:4 cement mortar (20mm thick) with proper slope wherever required including pointing of the joints with white Cement and machine pigments, curing etc. including 4" skirting wherever necessary. complete in all respects				

5	Electrical with UPS and data Cabling	Job	1.00		
	Providing And fixing, MK / CPL / Anchor /Crabtree havells or equivalent make modular switches / sockets, wires of Finoex, Polycab, Polyplast, Crabtee Havells or equivalent make, 5/15A 6pin socket with 16 A switch Camera, Text interface, Caed Access and comprising of 6A single switch complete with wiring complete as per satisfaction of Architect.				
	All necessary works including Updating of panel, Wiring, and cat-6 wire ,data point, M.C.B.,s and extension of power points (wherever required).				
	Total Amount				

Note: All rates are excluding G.S.T.

For GUNJAN & ASSOCIATES

 (Ar. GUNJAN KAPUR)
 PROPRIETOR

Ar. Gunjan Kapur

For M/s Gunjan & Associates